



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Red Sand
 Location: Kamala Phuket Depth: 2 m.
 Test Pit No.: KML_2.00Cliff Date: 06-12-03
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. Y1
 Weight of Container+Dry Sample g. 950.35
 Weight of Container g. 273.53
 Weight of Dry Sample g. 676.82

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	7.42	7.42	1.10	98.90
#8	2.36	14.30	21.72	3.21	96.79
#18	1.00	42.34	64.06	9.46	90.54
#40	0.43	133.95	198.01	29.26	70.74
#60	0.25	86.62	284.63	42.05	57.95
#80	0.18	30.58	315.21	46.57	53.43
#100	0.15	14.88	330.09	48.77	51.23
#140	0.106	28.94	359.03	53.05	46.95
#200	0.08	24.06	383.09	56.60	43.40
PAN	PAN	292.22	675.31	99.78	0.22



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY HYDROMETER TEST

PROJECT	Landslide Behavior in Phuket	OWNER		JOB NO.	
LOCATION	Patong Phuket	BORING NO.	PT3well	SAMPLE NO.	
SOIL DESCRIPTION	Brown Granitics Soil			DEPTH	3.00
TEST BY				DATE	23-12-04

SP. GR. OF SOIL =	2.64	SAMPLE WEIGHT	
HYDROMETER NO.	623	CAN NO.	M13
DISPERSING AGENT		DRY SOIL + CAN	438.83 gm.
MENISCUS CORRECTION		CAN WT.	384.17 gm.
% FINER THAN No. 200	39.91 %	WT. OF DRY SOIL	54.66 gm.

DATE	TIME	ELAPSED TIME, MIN	R _A	TEMP. °C	R _C	N %	h cm.	D mm.	N'%
18/12/2004		0.25	32	20	32.5	96.88	9.07	0.082	38.67
		0.5	30.7	20	31.2	93.01	9.47	0.059	37.12
		1	29.5	20	30	89.43	9.83	0.043	35.69
		2	27.5	20	28	83.47	10.44	0.031	33.31
		4	25.2	20	25.7	76.61	9.88	0.021	30.58
		8	22.5	20	23	68.56	10.71	0.016	27.36
		15	20.2	20	20.7	61.71	11.41	0.012	24.63
	14.35	30	17.2	20	17.7	52.76	12.33	0.009	21.06
	15.05	60	15	20	15.5	46.21	13.00	0.006	18.44
	16.05	120	12.5	20	13	38.75	13.76	0.005	15.47
19-12-04	10.15	1206	9.2	22	9.7	28.92	14.77	0.001	11.54
	12.15	1326	5.8	22	6.3	18.78	15.81	0.001	7.50
20-12-04	12.10	1449.15	5.5	22	6	17.89	15.90	0.001	7.14
	15.45	1653.1	5	22	5.5	16.40	16.05	0.001	6.54
21-12-04	13.00	2943.15	5	25	5.5	16.40	16.05	0.001	6.54
	16.15	3135.1	5	25	5.5	16.40	16.05	0.001	6.54
22-12-04	10.45	4230.15	4.8	25	5.3	15.80	16.11	0.001	6.31
	12.15	4335.1	4.8	25	5.3	15.80	16.11	0.001	6.31
23-12-04	10.40	5667.15	4.5	26	5	14.91	16.21	0.001	5.95
	12.30	5784.1	4.5	26	5	14.91	16.21	0.001	5.95

$$N = K_1 \cdot R_C$$

$$N' = N \cdot (\% \text{ Finer No. 200})$$

$$D = K_2 \cdot \sqrt{h/t}$$

$$R_C = R_a - C_M + C_T$$

Remarks: 1) Certification applies to test samples only.

2) Information under "For", "Project", are supplied by client. These are not certified.

3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Red Sand
 Location: Kamala Phuket Depth: 5 m.
 Test Pit No.: KML_5.00RCliff Date: 20/12/2003
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. x2
 Weight of Container+Dry Sample g. 849.07
 Weight of Container g. 250.42
 Weight of Dry Sample g. 598.65

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	3.42	3.42	0.57	99.43
#8	2.36	7.82	11.24	1.88	98.12
#18	1.00	49.70	60.94	10.18	89.82
#40	0.43	130.60	191.54	32.00	68.00
#60	0.25	85.66	277.20	46.30	53.70
#80	0.18	37.42	314.62	52.55	47.45
#100	0.15	21.52	336.14	56.15	43.85
#140	0.106	27.72	363.86	60.78	39.22
#200	0.08	23.22	387.08	64.66	35.34
PAN	PAN	209.43	596.51	99.64	0.36



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Red Sand
 Location: Kamala Phuket Depth: 5 m.
 Test Pit No.: KML_5.00LCliff Date: 28/12/2003
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. z6
 Weight of Container+Dry Sample g. 597.75
 Weight of Container g. 62.38
 Weight of Dry Sample g. 535.37

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	0.61	0.61	0.11	99.89
#8	2.36	6.09	6.70	1.25	98.75
#18	1.00	30.85	37.55	7.01	92.99
#40	0.43	151.31	188.86	35.28	64.72
#60	0.25	93.55	282.41	52.75	47.25
#80	0.18	42.19	324.60	60.63	39.37
#100	0.15	21.66	346.26	64.68	35.32
#140	0.106	22.55	368.81	68.89	31.11
#200	0.08	22.38	391.19	73.07	26.93
PAN	PAN	143.72	534.91	99.91	0.09



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Sand
 Location: Kamala Phuket Depth: 13 m.
 Test Pit No.: KML_13.00Cliff Date: 29-12-03
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. x2
 Weight of Container+Dry Sample g. 843.37
 Weight of Container g. 250.42
 Weight of Dry Sample g. 592.95

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	19.27	19.27	3.25	96.75
#8	2.36	46.03	65.30	11.01	88.99
#18	1.00	69.30	134.60	22.70	77.30
#40	0.43	147.13	281.73	47.51	52.49
#60	0.25	75.10	356.83	60.18	39.82
#80	0.18	34.25	391.08	65.95	34.05
#100	0.15	14.79	405.87	68.45	31.55
#140	0.106	26.02	431.89	72.84	27.16
#200	0.08	23.93	455.82	76.87	23.13
PAN	PAN	135.55	591.37	99.73	0.27



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Clayey Sand
 Location: Kamala Phuket Depth: 0.40 m.
 Test Pit No.: KML_0.40T1Well Date: 13/1/2004
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. z7
 Weight of Container+Dry Sample g. 493.23
 Weight of Container g. 140.1
 Weight of Dry Sample g. 353.13

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	41.25	41.25	11.68	88.32
#8	2.36	51.06	92.31	26.14	73.86
#18	1.00	26.02	118.33	33.51	66.49
#40	0.43	11.66	129.99	36.81	63.19
#60	0.25	7.62	137.61	38.97	61.03
#80	0.18	3.80	141.41	40.04	59.96
#100	0.15	2.19	143.60	40.66	59.34
#140	0.106	4.19	147.79	41.85	58.15
#200	0.08	4.33	152.12	43.08	56.92
PAN	PAN	201.21	353.33	100.06	-0.06



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Clayey Sand
 Location: Kamala Phuket Depth: 0.80 m.
 Test Pit No.: KML_0.80T2Well Date: 15-01-04
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. x2
 Weight of Container+Dry Sample g. 651.55
 Weight of Container g. 250.42
 Weight of Dry Sample g. 401.13

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	33.11	33.11	8.25	91.75
#8	2.36	74.80	107.91	26.90	73.10
#18	1.00	36.21	144.12	35.93	64.07
#40	0.43	16.30	160.42	39.99	60.01
#60	0.25	9.78	170.20	42.43	57.57
#80	0.18	6.56	176.76	44.07	55.93
#100	0.15	3.56	180.32	44.95	55.05
#140	0.106	6.99	187.31	46.70	53.30
#200	0.08	7.00	194.31	48.44	51.56
PAN	PAN	206.03	400.34	99.80	0.20



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Red Brown Clayey Sand
 Location: Kamala Phuket Depth: 1.20 m.
 Test Pit No.: KML_1.20T3Well Date: 07-01-04
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. z7
 Weight of Container+Dry Sample g. 550.81
 Weight of Container g. 140.1
 Weight of Dry Sample g. 410.71

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	21.57	21.57	5.25	94.75
#8	2.36	63.92	85.49	20.82	79.18
#18	1.00	45.33	130.82	31.85	68.15
#40	0.43	41.30	172.12	41.91	58.09
#60	0.25	31.52	203.64	49.58	50.42
#80	0.18	12.42	216.06	52.61	47.39
#100	0.15	7.13	223.19	54.34	45.66
#140	0.106	13.02	236.21	57.51	42.49
#200	0.08	11.88	248.09	60.41	39.59
PAN	PAN	161.93	410.02	99.83	0.17



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Granitics Soil
 Location: Kamala Phuket Depth: 2 m.
 Test Pit No.: KML_2.00T4Well Date: 04-01-04
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. x2
 Weight of Container+Dry Sample g. 615.48
 Weight of Container g. 250.42
 Weight of Dry Sample g. 365.06

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	9.61	9.61	2.63	97.37
#8	2.36	33.50	43.11	11.81	88.19
#18	1.00	46.44	89.55	24.53	75.47
#40	0.43	39.40	128.95	35.32	64.68
#60	0.25	25.29	154.24	42.25	57.75
#80	0.18	14.99	169.23	46.36	53.64
#100	0.15	6.03	175.26	48.01	51.99
#140	0.106	14.88	190.14	52.08	47.92
#200	0.08	15.05	205.19	56.21	43.79
PAN	PAN	158.92	364.11	99.74	0.26





KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Granitics Soil
 Location: Kamala Phuket Depth: 2.80 m.
 Test Pit No.: KML_2.80T5Well Date: 02-01-04
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. z7
 Weight of Container+Dry Sample g. 617.1
 Weight of Container g. 140.1
 Weight of Dry Sample g. 477.00

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	18.16	18.16	3.81	96.19
#8	2.36	56.59	74.75	15.67	84.33
#18	1.00	68.43	143.18	30.02	69.98
#40	0.43	75.78	218.96	45.90	54.10
#60	0.25	43.31	262.27	54.98	45.02
#80	0.18	20.43	282.70	59.27	40.73
#100	0.15	11.13	293.83	61.60	38.40
#140	0.106	21.44	315.27	66.09	33.91
#200	0.08	15.17	330.44	69.27	30.73
PAN	PAN	146.06	476.50	99.90	0.10



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Clayey Sand
 Location: Patong Phuket Depth: 1 m.
 Test Pit No.: PT_1.00Well Date: 14/11/2003
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. Y2
 Weight of Container+Dry Sample g. 767.35
 Weight of Container g. 156.18
 Weight of Dry Sample g. 611.17

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	1.61	1.61	0.26	99.74
#8	2.36	10.27	11.88	1.94	98.06
#18	1.00	97.00	108.88	17.82	82.18
#40	0.43	117.98	226.86	37.12	62.88
#60	0.25	32.42	259.28	42.42	57.58
#80	0.18	16.75	276.03	45.16	54.84
#100	0.15	5.86	281.89	46.12	53.88
#140	0.106	12.11	294.00	48.10	51.90
#200	0.08	33.05	327.05	53.51	46.49
PAN	PAN	282.98	610.03	99.81	0.19



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Clayey Sand
 Location: Patong Phuket Depth: 1.30 m.
 Test Pit No.: PT_1.30Well Date: 21/11/2003
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. Y1
 Weight of Container+Dry Sample g. 1039.57
 Weight of Container g. 460.75
 Weight of Dry Sample g. 578.82

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
1/2"	12.50	7.88	7.88	1.36	98.64
#4	4.75	4.69	12.57	2.17	97.83
#8	2.36	14.68	27.25	4.71	95.29
#18	1.00	66.47	93.72	16.19	83.81
#40	0.43	106.39	200.11	34.57	65.43
#60	0.25	30.93	231.04	39.92	60.08
#80	0.18	13.01	244.05	42.16	57.84
#100	0.15	0.00	244.05	42.16	57.84
#140	0.106	14.44	258.49	44.66	55.34
#200	0.08	21.15	279.64	48.31	51.69
PAN	PAN	291.19	570.83	98.62	1.38



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Granitics Soil
 Location: Patong Phuket Depth: 2.50 m.
 Test Pit No.: PT_2.50Well Date: 04-12-03
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. Y1
 Weight of Container+Dry Sample g. 1209.07
 Weight of Container g. 460.75
 Weight of Dry Sample g. 748.32

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	1.89	1.89	0.25	99.75
#8	2.36	4.04	5.93	0.79	99.21
#18	1.00	88.91	94.84	12.67	87.33
#40	0.43	187.73	282.57	37.76	62.24
#60	0.25	58.20	340.77	45.54	54.46
#80	0.18	25.20	365.97	48.91	51.09
#100	0.15	18.54	384.51	51.38	48.62
#140	0.106	36.23	420.74	56.22	43.78
#200	0.08	36.12	456.86	61.05	38.95
PAN	PAN	286.15	743.01	99.29	0.71



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Granitics Soil
 Location: Patong Phuket Depth: 3 m.
 Test Pit No.: PT_3.00Well Date: 11-12-03
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. Y1
 Weight of Container+Dry Sample g. 1203.4
 Weight of Container g. 460.75
 Weight of Dry Sample g. 742.65

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	1.42	1.42	0.19	99.81
#8	2.36	9.27	10.69	1.44	98.56
#18	1.00	79.37	90.06	12.13	87.87
#40	0.43	198.13	288.19	38.81	61.19
#60	0.25	55.70	343.89	46.31	53.69
#80	0.18	26.13	370.02	49.82	50.18
#100	0.15	10.36	380.38	51.22	48.78
#140	0.106	32.10	412.48	55.54	44.46
#200	0.08	33.77	446.25	60.09	39.91
PAN	PAN	284.52	730.77	98.40	1.60



D10= D30 = D60 =

Remarks:
 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Granitics Soil
 Location: Patong Phuket Depth: 3.50 m.
 Test Pit No.: PT_3.50Well Date: 20/11/2003
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. x2
 Weight of Container+Dry Sample g. 758.7
 Weight of Container g. 156.13
 Weight of Dry Sample g. 602.57

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	3.84	3.84	0.64	99.36
#8	2.36	6.49	10.33	1.71	98.29
#18	1.00	92.70	103.03	17.10	82.90
#40	0.43	141.68	244.71	40.61	59.39
#60	0.25	44.97	289.68	48.07	51.93
#80	0.18	25.29	314.97	52.27	47.73
#100	0.15	13.36	328.33	54.49	45.51
#140	0.106	34.07	362.40	60.14	39.86
#200	0.08	32.29	394.69	65.50	34.50
PAN	PAN	206.54	601.23	99.78	0.22



D10= D30 = D60 =

- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Granitics Soil
 Location: Patong Phuket Depth: 4 m.
 Test Pit No.: PT_4.00Well Date: 22/11/2003
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. x2
 Weight of Container+Dry Sample g. 771.1
 Weight of Container g. 156.13
 Weight of Dry Sample g. 614.97

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	0.96	0.96	0.16	99.84
#8	2.36	5.38	6.34	1.03	98.97
#18	1.00	92.45	98.79	16.06	83.94
#40	0.43	141.85	240.64	39.13	60.87
#60	0.25	40.29	280.93	45.68	54.32
#80	0.18	29.74	310.67	50.52	49.48
#100	0.15	12.57	323.24	52.56	47.44
#140	0.106	30.47	353.71	57.52	42.48
#200	0.08	29.76	383.47	62.36	37.64
PAN	PAN	229.87	613.34	99.73	0.27



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Clayey Sand
 Location: Patong Phuket Depth: 1.80 m.
 Test Pit No.: PT_1.80LS Date: 07-12-03
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. Y1
 Weight of Container+Dry Sample g. 1000.42
 Weight of Container g. 460.75
 Weight of Dry Sample g. 539.67

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	6.12	6.12	1.13	98.87
#8	2.36	41.23	47.35	8.77	91.23
#18	1.00	78.18	125.53	23.26	76.74
#40	0.43	68.67	194.20	35.98	64.02
#60	0.25	25.04	219.24	40.62	59.38
#80	0.18	6.60	225.84	41.85	58.15
#100	0.15	3.43	229.27	42.48	57.52
#140	0.106	11.02	240.29	44.53	55.47
#200	0.08	8.77	249.06	46.15	53.85
PAN	PAN	289.03	538.09	99.71	0.29



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Brown Sand
 Location: Patong Phuket Depth: 4 m.
 Test Pit No.: PT_4.00LS Date: 13/12/2003
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. x2
 Weight of Container+Dry Sample g. 847.07
 Weight of Container g. 250.42
 Weight of Dry Sample g. 596.65

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	17.84	17.84	2.99	97.01
#8	2.36	50.25	68.09	11.41	88.59
#18	1.00	74.52	142.61	23.90	76.10
#40	0.43	98.18	240.79	40.36	59.64
#60	0.25	32.71	273.50	45.84	54.16
#80	0.18	16.18	289.68	48.55	51.45
#100	0.15	6.64	296.32	49.66	50.34
#140	0.106	21.22	317.54	53.22	46.78
#200	0.08	12.82	330.36	55.37	44.63
PAN	PAN	264.00	594.36	99.62	0.38



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Red Brown Sand
 Location: Patong Phuket Depth: 7 m.
 Test Pit No.: PT_7.00LS Date: 07-12-03
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. x2
 Weight of Container+Dry Sample g. 773.72
 Weight of Container g. 156.13
 Weight of Dry Sample g. 617.59

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	5.99	5.99	0.97	99.03
#8	2.36	26.36	32.35	5.24	94.76
#18	1.00	64.20	96.55	15.63	84.37
#40	0.43	149.07	245.62	39.77	60.23
#60	0.25	62.05	307.67	49.82	50.18
#80	0.18	24.44	332.11	53.78	46.22
#100	0.15	18.04	350.15	56.70	43.30
#140	0.106	22.54	372.69	60.35	39.65
#200	0.08	33.58	406.27	65.78	34.22
PAN	PAN	208.02	614.29	99.47	0.53



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


SIEVE ANALYSIS (ASTM C136)

Project: Landslide Behavior in Phuket
 For: Stability Analysis
 Description of Sample: Red Brown Sand
 Location: Patong Phuket Depth: 10 m.
 Test Pit No.: PT_10.00LS Date: 21/12/2003
 Tested by: THIPMANEE

SAMPLE WEIGHT

Container No. X2
 Weight of Container+Dry Sample g. 829.72
 Weight of Container g. 250.42
 Weight of Dry Sample g. 579.30

Sieve No.	Sieve Opening	Weight of Soil Retained, g	Cumulative Retained, g	Cumulative Retained, %	Percent Finer
3/8"	9.53	0	0	0	100
#4	4.75	1.83	1.83	0.32	99.68
#8	2.36	3.61	5.44	0.94	99.06
#18	1.00	55.92	61.36	10.59	89.41
#40	0.43	154.55	215.91	37.27	62.73
#60	0.25	79.59	295.50	51.01	48.99
#80	0.18	41.42	336.92	58.16	41.84
#100	0.15	34.26	371.18	64.07	35.93
#140	0.106	39.41	410.59	70.88	29.12
#200	0.08	36.51	447.10	77.18	22.82
PAN	PAN	130.60	577.70	99.72	0.28



D10= D30 = D60 =

Remarks:

- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST


PROJECT	Landslide Behavior in Phuket	Location	Kamala Phuket
Borehole No.	KML_0.40T1Well	Sample No.	1
Soil Description	Red Clay	Depth	0.40 m.
Test by	THIPMANEE	Date	13/1/2004

Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	65	55	42	34	29	25	19	13
Wt. Flask+Water	654.62	656.66	659.34	660.46	661.29	661.53	662.37	662.68

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 25	25.5						
Flask+Water	g. 661.67	661.61						
Flask+Water+Soil	g. 687.71	686.37						
Container No.	x3	x3						
Dry Soil+Container	g. 193.7	191.95						
Weight of Container	g. 151.78	151.78						
Dry Soil	g. 41.92	40.17						
Specific Gravity of Water	0.9971	0.9970						
Specific Gravity of Soil	2.633	2.599						
Average Specific Gravity of Soil	2.616							



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Kamala Phuket
Borehole No.	KML_0.80T2Well	Sample No.	1
Soil Description	Red Clay	Depth	0.80 m.
Test by	THIPMANEE	Date	13/1/2004


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	63	54	42	35	29	25	16	10
Wt. Flask+Water	650.86	652.86	655.32	656.34	657.28	657.71	658.57	658.82

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 25.5	25.5						
Flask+Water	g. 657.64	657.64						
Flask+Water+Soil	g. 682.08	682.74						
Container No.	x1	x1						
Dry Soil+Container	g. 193.54	194.82						
Weight of Container	g. 154.12	154.12						
Dry Soil	g. 39.42	40.7						
Specific Gravity of Water	0.99695	0.9970						
Specific Gravity of Soil	2.623	2.601						
Average Specific Gravity of Soil	2.612							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Kamala Phuket
Borehole No.	KML_1.20T3Well	Sample No.	1
Soil Description	Red Clayey Sand	Depth	1.20 m.
Test by	THIPMANEE	Date	07-01-04


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	65	55	42	34	29	25	19	13
Wt. Flask+Water	654.62	656.66	659.34	660.46	661.29	661.53	662.37	662.68

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 24.5	24						
Flask+Water	g. 661.72	661.77						
Flask+Water+Soil	g. 692.95	692.98						
Container No.	x3	x3						
Dry Soil+Container	g. 202.06	202.02						
Weight of Container	g. 151.78	151.78						
Dry Soil	g. 50.28	50.24						
Specific Gravity of Water	0.9972	0.9973						
Specific Gravity of Soil	2.632	2.632						
Average Specific Gravity of Soil	2.632							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY


DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Kamala Phuket
Borehole No.	KML_2.00T4Well	Sample No.	1
Soil Description	Brown Granitics Soil	Depth	2.00 m.
Test by	THIPMANEE	Date	07-01-04

Flask Calibration								
Determination No.	1	2	3	4	5	6	7	8
Temperature	63	54	42	35	29	25	16	10
Wt. Flask+Water	650.86	652.86	655.32	656.34	657.28	657.71	658.57	658.82

SPECIFIC GRAVITY DETERMINATION								
Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 24.5	24						
Flask+Water	g. 657.75	657.80						
Flask+Water+Soil	g. 683.09	679.69						
Container No.	x1	x1						
Dry Soil+Container	g. 195.2	189.53						
Weight of Container	g. 154.12	154.12						
Dry Soil	g. 41.08	35.41						
Specific Gravity of Water	0.9972	0.9973						
Specific Gravity of Soil	2.603	2.612						
Average Specific Gravity of Soil	2.607							



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Kamala Phuket
Borehole No.	KML_2.80T5Well	Sample No.	1
Soil Description	Brown Granitics Soil	Depth	2.80 m.
Test by	THIPMANEE	Date	04-01-04


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	65	55	42	34	29	25	19	13
Wt. Flask+Water	654.62	656.66	659.34	660.46	661.29	661.53	662.37	662.68

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 28	23.5						
Flask+Water	g. 661.32	661.83						
Flask+Water+Soil	g. 692.48	693.08						
Container No.	x3	z6						
Dry Soil+Container	g. 201.96	112.41						
Weight of Container	g. 151.78	62.38						
Dry Soil	g. 50.18	50.03						
Specific Gravity of Water	0.9963	0.9975						
Specific Gravity of Soil	2.628	2.658						
Average Specific Gravity of Soil	2.643							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Kamala Phuket
Borehole No.	KML_2.00Cliff	Sample No.	1
Soil Description	Red Sand	Depth	2.00 m.
Test by	THIPMANEE	Date	04-01-04


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	63	54	42	35	29	25	16	10
Wt. Flask+Water	650.86	652.86	655.32	656.34	657.28	657.71	658.57	658.82

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 28	23.5						
Flask+Water	g. 657.35	657.85						
Flask+Water+Soil	g. 688.42	689.07						
Container No.	x1	z1						
Dry Soil+Container	g. 204.27	111.86						
Weight of Container	g. 154.12	61.85						
Dry Soil	g. 50.15	50.01						
Specific Gravity of Water	0.9963	0.9975						
Specific Gravity of Soil	2.618	2.654						
Average Specific Gravity of Soil	2.636							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Kamala Phuket
Borehole No.	KML_5.00RCliff	Sample No.	1
Soil Description	Red Sand	Depth	5.00 m.
Test by	THIPMANEE	Date	28/12/2003


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	63	54	42	35	29	25	16	10
Wt. Flask+Water	650.86	652.86	655.32	656.34	657.28	657.71	658.57	658.82

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature C°	26	27						
Flask+Water g.	657.59	657.47						
Flask+Water+Soil g.	688.85	688.69						
Container No.	z1	x1						
Dry Soil+Container g.	112.14	204.34						
Weight of Container g.	61.85	154.12						
Dry Soil g.	50.29	50.22						
Specific Gravity of Water	0.9968	0.9965						
Specific Gravity of Soil	2.635	2.634						
Average Specific Gravity of Soil	2.634							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Kamala Phuket
Borehole No.	KML_5.00Cliff	Sample No.	1
Soil Description	Red Sand	Depth	5.00 m.
Test by	THIPMANEE	Date	29/12/2003


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	63	54	42	35	29	25	16	10
Wt. Flask+Water	650.86	652.86	655.32	656.34	657.28	657.71	658.57	658.82

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 25.5	27.5						
Flask+Water	g. 657.64	657.41						
Flask+Water+Soil	g. 688.77	688.45						
Container No.	x1	x1						
Dry Soil+Container	g. 204.33	204.31						
Weight of Container	g. 154.12	154.12						
Dry Soil	g. 50.21	50.19						
Specific Gravity of Water	0.99695	0.9964						
Specific Gravity of Soil	2.623	2.611						
Average Specific Gravity of Soil	2.617							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Kamala Phuket
Borehole No.	KML_13.00Cliff	Sample No.	1
Soil Description	Brown Sand	Depth	13.00 m.
Test by	THIPMANEE	Date	29/12/2003


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	65	55	42	34	29	25	19	13
Wt. Flask+Water	654.62	656.66	659.34	660.46	661.29	661.53	662.37	662.68

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 25.5	27.5						
Flask+Water	g. 661.61	661.38						
Flask+Water+Soil	g. 692.88	692.55						
Container No.	x3	x3						
Dry Soil+Container	g. 201.99	202.04						
Weight of Container	g. 151.78	151.78						
Dry Soil	g. 50.21	50.26						
Specific Gravity of Water	0.99695	0.9964						
Specific Gravity of Soil	2.643	2.623						
Average Specific Gravity of Soil	2.633							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_1.00Well	Sample No.	1
Soil Description	Brown Clayey Sand	Depth	1.00 m.
Test by	THIPMANEE	Date	15/12/2003


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	63	54	42	35	29	25	16	10
Wt. Flask+Water	650.86	652.86	655.32	656.34	657.28	657.71	658.57	658.82

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 28.5	26.5						
Flask+Water	g. 657.29	657.53						
Flask+Water+Soil	g. 688.9	688.88						
Container No.	x1	x1						
Dry Soil+Container	g. 204.57	204.48						
Weight of Container	g. 154.31	154.31						
Dry Soil	g. 50.26	50.17						
Specific Gravity of Water	0.99615	0.9967						
Specific Gravity of Soil	2.684	2.657						
Average Specific Gravity of Soil	2.670							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST


PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_1.30Well	Sample No.	1
Soil Description	Brown Clayey Sand	Depth	1.30 m.
Test by	THIPMANEE	Date	13/12/2003

Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	65	55	42	34	29	25	19	13
Wt. Flask+Water	654.62	656.66	659.34	660.46	661.29	661.53	662.37	662.68

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 27	27						
Flask+Water	g. 661.44	661.44						
Flask+Water+Soil	g. 692.86	692.5						
Container No.	x3	z1						
Dry Soil+Container	g. 202.11	111.92						
Weight of Container	g. 151.90	61.95						
Dry Soil	g. 50.21	49.97						
Specific Gravity of Water	0.9965	0.9965						
Specific Gravity of Soil	2.663	2.633						
Average Specific Gravity of Soil	2.648							



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_2.00Well	Sample No.	1
Soil Description	Red Clayey Sand	Depth	2.00 m.
Test by	THIPMANEE	Date	21/12/2003


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	63	54	42	35	29	25	16	10
Wt. Flask+Water	650.86	652.86	655.32	656.34	657.28	657.71	658.57	658.82

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 25	29						
Flask+Water	g. 657.70	657.23						
Flask+Water+Soil	g. 688.86	688.6						
Container No.	x1	x1						
Dry Soil+Container	g. 204.29	204.35						
Weight of Container	g. 154.31	154.31						
Dry Soil	g. 49.98	50.04						
Specific Gravity of Water	0.9971	0.9960						
Specific Gravity of Soil	2.649	2.669						
Average Specific Gravity of Soil	2.659							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_2.50Well	Sample No.	1
Soil Description	Brown Granitics Soil	Depth	2.50 m.
Test by	THIPMANEE	Date	13/12/2003


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	63	54	42	35	29	25	16	10
Wt. Flask+Water	650.86	652.86	655.32	656.34	657.28	657.71	658.57	658.82

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 27	27						
Flask+Water	g. 657.47	657.47						
Flask+Water+Soil	g. 688.63	688.56						
Container No.	x1	z6						
Dry Soil+Container	g. 204.39	112.32						
Weight of Container	g. 154.31	62.38						
Dry Soil	g. 50.08	49.94						
Specific Gravity of Water	0.9965	0.9965						
Specific Gravity of Soil	2.637	2.640						
Average Specific Gravity of Soil	2.639							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST


PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_3.00Well	Sample No.	1
Soil Description	Brown Granitics Soil	Depth	3.00 m.
Test by	THIPMANEE	Date	21/12/2003

Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	65	55	42	34	29	25	19	13
Wt. Flask+Water	654.62	656.66	659.34	660.46	661.29	661.53	662.37	662.68

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 24.5	28.5						
Flask+Water	g. 661.72	661.26						
Flask+Water+Soil	g. 692.77	692.41						
Container No.	x3	x3						
Dry Soil+Container	g. 201.88	201.89						
Weight of Container	g. 151.90	151.90						
Dry Soil	g. 49.98	49.99						
Specific Gravity of Water	0.9972	0.9962						
Specific Gravity of Soil	2.633	2.643						
Average Specific Gravity of Soil	2.638							



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_3.50Well	Sample No.	1
Soil Description	Brown Granitics Soil	Depth	3.50 m.
Test by	THIPMANEE	Date	10-12-03


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	63	54	42	35	29	25	16	10
Wt. Flask+Water	650.86	652.86	655.32	656.34	657.28	657.71	658.57	658.82

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 28	28.5						
Flask+Water	g. 657.35	657.29						
Flask+Water+Soil	g. 684.4	688.42						
Container No.	x3	x3						
Dry Soil+Container	g. 195.51	201.92						
Weight of Container	g. 151.90	151.90						
Dry Soil	g. 43.61	50.02						
Specific Gravity of Water	0.9963	0.9962						
Specific Gravity of Soil	2.623	2.637						
Average Specific Gravity of Soil	2.630							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST


PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_4.00Well	Sample No.	1
Soil Description	Brown Granitics Soil	Depth	4.00 m.
Test by	THIPMANEE	Date	07-12-03

Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	65	55	42	34	29	25	19	13
Wt. Flask+Water	654.62	656.66	659.34	660.46	661.29	661.53	662.37	662.68

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 28	28						
Flask+Water	g. 661.32	661.32						
Flask+Water+Soil	g. 692.28	692.4						
Container No.	x1	x1						
Dry Soil+Container	g. 203.8	204.31						
Weight of Container	g. 154.31	154.31						
Dry Soil	g. 49.49	50						
Specific Gravity of Water	0.9963	0.9963						
Specific Gravity of Soil	2.661	2.633						
Average Specific Gravity of Soil	2.647							



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY


DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_1.80Cliff	Sample No.	1
Soil Description	Brown Clayey Sand	Depth	1.80 m.
Test by	THIPMANEE	Date	15/12/2003

Flask Calibration								
Determination No.	1	2	3	4	5	6	7	8
Temperature	65	55	42	34	29	25	19	13
Wt. Flask+Water	654.62	656.66	659.34	660.46	661.29	661.53	662.37	662.68

SPECIFIC GRAVITY DETERMINATION								
Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 28.5	26.5						
Flask+Water	g. 661.26	661.50						
Flask+Water+Soil	g. 692.61	692.65						
Container No.	x3	x3						
Dry Soil+Container	g. 202.15	202.06						
Weight of Container	g. 151.90	151.90						
Dry Soil	g. 50.25	50.16						
Specific Gravity of Water	0.99615	0.9967						
Specific Gravity of Soil	2.648	2.630						
Average Specific Gravity of Soil	2.639							



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_4.00Cliff	Sample No.	1
Soil Description	Brown Sand	Depth	4.00 m.
Test by	THIPMANEE	Date	20/12/2003


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	63	54	42	35	29	25	16	10
Wt. Flask+Water	650.86	652.86	655.32	656.34	657.28	657.71	658.57	658.82

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 26.5	26.5						
Flask+Water	g. 657.53	657.53						
Flask+Water+Soil	g. 688.67	688.8						
Container No.	x1	x1						
Dry Soil+Container	g. 204.39	204.36						
Weight of Container	g. 154.31	154.31						
Dry Soil	g. 50.08	50.05						
Specific Gravity of Water	0.99665	0.9967						
Specific Gravity of Soil	2.635	2.656						
Average Specific Gravity of Soil	2.646							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_7.00Cliff	Sample No.	1
Soil Description	Red Brown Sand	Depth	7.00 m.
Test by	THIPMANEE	Date	20/12/2003


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	65	55	42	34	29	25	19	13
Wt. Flask+Water	654.62	656.66	659.34	660.46	661.29	661.53	662.37	662.68

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 26.5	26.5						
Flask+Water	g. 661.50	661.50						
Flask+Water+Soil	g. 692.76	692.76						
Container No.	x3	x3						
Dry Soil+Container	g. 201.99	202.04						
Weight of Container	g. 151.90	151.90						
Dry Soil	g. 50.09	50.14						
Specific Gravity of Water	0.99665	0.9967						
Specific Gravity of Soil	2.652	2.647						
Average Specific Gravity of Soil	2.649							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

SPECIFIC GRAVITY TEST

PROJECT	Landslide Behavior in Phuket	Location	Patong Phuket
Borehole No.	PT_10.00Cliff	Sample No.	1
Soil Description	Red Brown Sand	Depth	10.00 m.
Test by	THIPMANEE	Date	28/12/2003


Flask Calibration

Determination No.	1	2	3	4	5	6	7	8
Temperature	65	55	42	34	29	25	19	13
Wt. Flask+Water	654.62	656.66	659.34	660.46	661.29	661.53	662.37	662.68

SPECIFIC GRAVITY DETERMINATION

Determination No.	1	2	3	4	5	6	7	8
Temperature	C° 26	27						
Flask+Water	g. 661.55	661.44						
Flask+Water+Soil	g. 692.83	692.72						
Container No.	z6	x3						
Dry Soil+Container	g. 112.54	201.87						
Weight of Container	g. 62.38	151.90						
Dry Soil	g. 50.16	49.97						
Specific Gravity of Water	0.9968	0.9965						
Specific Gravity of Soil	2.648	2.664						
Average Specific Gravity of Soil	2.656							

Calibration of Volumetric Flask



- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Kamala Phuket
 Borehole No. KML_0.40T1Well Sample No. 1 Depth 0.40 m
 Soil Description Red Clay Tested by THIPMANEE Date 9-2-04

Plastic Limit

Container No.		s19	s2	s4	s21	s15
Weight of Wet Soil+Container	g	6.95	9.65	10.34	8.02	11.57
Weight of Dry Soil+Container	g	6.42	8.38	8.93	7.25	9.90
Weight of Container	g	4.97	4.86	4.94	4.98	4.93
Weight of Water	g	0.53	1.27	1.41	0.77	1.67
Weight of Dry Soil	g	1.45	3.52	3.99	2.27	4.97
Water Content, W	%	36.55	36.08	35.34	33.92	33.60
Average	%	35.10				

Liquid Limit

Number of Blows		12	18	24	28	34	44
Container No.		s25	s16	s10	s24	s22	s8
Weight of Wet Soil+Container	g	13.40	12.51	13.47	15.02	13.67	12.93
Weight of Dry Soil+Container	g	10.2	9.78	10.5	11.51	10.68	10.34
Weight of Container	g	4.96	5.02	5.01	4.93	4.96	4.93
Weight of Water	g	3.20	2.73	2.97	3.51	2.99	2.59
Weight of Dry Soil	g	5.24	4.76	5.49	6.58	5.72	5.41
Water Content, W	%	61.07	57.35	54.10	53.34	52.27	47.87



Liquid Limit, LL = 54.15 %
 Plastic Limit, PL = 35.10 %
 Plasticity Index, PI = 19.05 %
 Water content, W_n = _____ %

- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Kamala Phuket
 Borehole No. KML_0.80T2Well Sample No. 1 Depth 0.80 m
 Soil Description Red Clay Tested by THIPMANEE Date 9-2-04

Plastic Limit

Container No.		s9	s13	s5	s3
Weight of Wet Soil+Container	g	10.71	9.22	10.66	9.47
Weight of Dry Soil+Container	g	9.31	8.20	9.28	8.37
Weight of Container	g	4.91	4.90	4.91	4.94
Weight of Water	g	1.40	1.02	1.38	1.10
Weight of Dry Soil	g	4.40	3.30	4.37	3.43
Water Content, W	%	31.82	30.91	31.58	32.07
Average	%	31.59			

Liquid Limit

Number of Blows		12	16	21	37	38
Container No.		s14	s12	s26	s20	s1
Weight of Wet Soil+Container	g	16.35	13.12	14.35	12.65	11.69
Weight of Dry Soil+Container	g	12.42	10.36	11.25	10.27	9.68
Weight of Container	g	5.05	4.95	4.90	4.90	4.95
Weight of Water	g	3.93	2.76	3.1	2.38	2.01
Weight of Dry Soil	g	7.37	5.41	6.35	5.37	4.73
Water Content, W	%	53.32	51.02	48.82	44.32	42.49



Liquid Limit, LL = 47.04 %
 Plastic Limit, PL = 31.59 %
 Plasticity Index, PI = 15.44 %
 Water content, W_n = _____ %

Remarks: 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Kamala Phuket
 Borehole No. KML_1.20T3Well Sample No. 1 Depth 1.20 m
 Soil Description Red Clayey Sand Tested by THIPMANEE Date 11-2-04

Plastic Limit

Container No.		s17	s25	s6	s14
Weight of Wet Soil+Container	g	10.06	13.40	11.71	10.53
Weight of Dry Soil+Container	g	8.93	11.57	10.30	9.41
Weight of Container	g	4.93	4.96	4.96	5.05
Weight of Water	g	1.13	1.83	1.41	1.12
Weight of Dry Soil	g	4.00	6.61	5.34	4.36
Water Content, W	%	28.25	27.69	26.40	25.69
Average	%	27.01			

Liquid Limit

Number of Blows		16	19	29	36	44
Container No.		s3	s13	s11	s9	s10
Weight of Wet Soil+Container	g	14.10	12.22	15.53	12.89	13.40
Weight of Dry Soil+Container	g	11.52	10.22	12.8	10.82	11.26
Weight of Container	g	4.94	4.90	5.27	4.91	5.01
Weight of Water	g	2.58	2.00	2.73	2.07	2.14
Weight of Dry Soil	g	6.58	5.32	7.53	5.91	6.25
Water Content, W	%	39.21	37.59	36.25	35.03	34.24



Liquid Limit, LL = 36.80 %
 Plastic Limit, PL = 27.01 %
 Plasticity Index, PI = 9.79 %
 Water content, W_n = _____ %

Remarks: 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Kamala Phuket
 Borehole No. KML_2.00T4Well Sample No. 1 Depth 2.00 m
 Soil Description Brown Granitics Soil Tested by THIPMANEE Date 2-11-04

Plastic Limit

Container No.		s19	s21	s4	s12
Weight of Wet Soil+Container	g	9.55	8.76	9.47	8.45
Weight of Dry Soil+Container	g	8.63	7.98	8.49	7.69
Weight of Container	g	4.97	4.98	4.94	4.96
Weight of Water	g	0.92	0.78	0.98	0.76
Weight of Dry Soil	g	3.66	3.00	3.55	2.73
Water Content, W	%	25.14	26.00	27.61	27.84
Average	%	26.65			

Liquid Limit

Number of Blows		14	22	31	44
Container No.		s2	s24	s5	s16
Weight of Wet Soil+Container	g	12.59	13.22	14.57	14.35
Weight of Dry Soil+Container	g	10.76	11.32	12.42	12.3
Weight of Container	g	4.86	4.93	4.91	5.02
Weight of Water	g	1.83	1.90	2.15	2.05
Weight of Dry Soil	g	5.90	6.39	7.51	7.28
Water Content, W	%	31.02	29.73	28.63	28.16



Liquid Limit, LL = 29.43 %
 Plastic Limit, PL = 26.65 %
 Plasticity Index, PI = 2.79 %
 Water content, W_n = _____ %

Remarks: 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Kamala Phuket
 Borehole No. KML_2.00Cliff Sample No. 1 Depth 2.00 m
 Soil Description Red Sand Tested by THIPMANEE Date 30/1/2004

Plastic Limit

Container No.	s12	s10	s18	s26	
Weight of Wet Soil+Container	g 9.28	7.70	8.65	9.44	
Weight of Dry Soil+Container	g 8.38	7.13	7.81	8.52	
Weight of Container	g 4.95	5.01	4.91	4.89	
Weight of Water	g 0.90	0.57	0.84	0.92	
Weight of Dry Soil	g 3.43	2.12	2.90	3.63	
Water Content, W	% 26.24	26.89	28.97	25.34	
Average	% 26.86				

Liquid Limit

Number of Blows	15	22	25	30	38	46
Container No.	s19	s20	s15	s8	s7	s25
Weight of Wet Soil+Container	g 16.32	16.94	17.75	14.50	16.17	15.97
Weight of Dry Soil+Container	g 13.55	14.09	14.72	12.27	13.64	13.5
Weight of Container	g 4.97	4.90	4.93	4.93	4.92	4.96
Weight of Water	g 2.77	2.85	3.03	2.23	2.53	2.47
Weight of Dry Soil	g 8.58	9.19	9.79	7.34	8.72	8.54
Water Content, W	% 32.28	31.01	30.95	30.38	29.01	28.92



Liquid Limit, LL = 30.73 %
 Plastic Limit, PL = 26.86 %
 Plasticity Index, PI = 3.87 %
 Water content, W_n = _____ %

Remarks: 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Patong Phuket
 Borehole No. PT_1.00Well Sample No. 1 Depth 1.00 m
 Soil Description Brown Clayey Sand Tested by THIPMANEE Date 17/1/2004

Plastic Limit

Container No.		s2	s9	s17	s4
Weight of Wet Soil+Container	g	14.13	11.73	8.64	8.26
Weight of Dry Soil+Container	g	11.97	10.15	7.79	7.53
Weight of Container	g	4.85	4.91	4.93	4.94
Weight of Water	g	2.16	1.58	0.85	0.73
Weight of Dry Soil	g	7.12	5.24	2.86	2.59
Water Content, W	%	30.34	30.15	29.72	28.19
Average	%	29.60			

Liquid Limit

Number of Blows		12	27	32	50
Container No.		s1	s12	s10	s16
Weight of Wet Soil+Container	g	16.27	15.84	18.33	22.31
Weight of Dry Soil+Container	g	12.99	12.89	14.84	17.91
Weight of Container	g	4.94	4.96	5.01	5.04
Weight of Water	g	3.28	2.95	3.49	4.4
Weight of Dry Soil	g	8.05	7.93	9.83	12.87
Water Content, W	%	40.75	37.20	35.50	34.19



Liquid Limit, LL = 37.24 %
 Plastic Limit, PL = 29.60 %
 Plasticity Index, PI = 7.64 %
 Water content, W_n = _____ %

Remarks: 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Patong Phuket
 Borehole No. PT_1.30Well Sample No. 1 Depth 1.30 m
 Soil Description Brown Clayey Sand Tested by THIPMANEE Date 26/1/2004

Plastic Limit

Container No.	s4	s1	s16	s6	
Weight of Wet Soil+Container	g 8.17	8.58	8.04	8.00	
Weight of Dry Soil+Container	g 7.43	7.77	7.38	7.33	
Weight of Container	g 4.94	4.95	5.02	4.97	
Weight of Water	g 0.74	0.81	0.66	0.67	
Weight of Dry Soil	g 2.49	2.82	2.36	2.36	
Water Content, W	% 29.72	28.72	27.97	28.39	
Average	% 28.70				

Liquid Limit

Number of Blows	13	16	26	30	35	40
Container No.	s17	s9	s3	s2	s14	s5
Weight of Wet Soil+Container	g 16.74	16.64	18.30	15.59	15.55	18.85
Weight of Dry Soil+Container	g 13.48	13.43	14.78	12.78	12.85	15.3
Weight of Container	g 4.93	4.91	4.94	4.86	5.05	4.91
Weight of Water	g 3.26	3.21	3.52	2.81	2.70	3.55
Weight of Dry Soil	g 8.55	8.52	9.84	7.92	7.80	10.39
Water Content, W	% 38.13	37.68	35.77	35.48	34.62	34.17



Liquid Limit, LL = 35.93 %
 Plastic Limit, PL = 28.70 %
 Plasticity Index, PI = 7.23 %
 Water content, W_n = _____ %

Remarks: 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Patong Phuket
 Borehole No. PT_2.00Well Sample No. 1 Depth 2.00 m
 Soil Description Red Clayey Sand Tested by THIPMANEE Date 17/1/2004

Plastic Limit

Container No.		s2	s3	s10	s1
Weight of Wet Soil+Container	g	8.39	6.92	8.78	6.94
Weight of Dry Soil+Container	g	7.55	6.45	7.85	6.46
Weight of Container	g	4.88	4.95	5.02	4.95
Weight of Water	g	0.84	0.47	0.93	0.48
Weight of Dry Soil	g	2.67	1.50	2.83	1.51
Water Content, W	%	31.46	31.33	32.86	31.79
Average	%	31.86			

Liquid Limit

Number of Blows		12	26	36	40
Container No.		s4	s5	s8	s12
Weight of Wet Soil+Container	g	19.47	19.83	17.08	20.60
Weight of Dry Soil+Container	g	15.22	15.78	13.86	16.55
Weight of Container	g	4.95	4.92	4.94	4.97
Weight of Water	g	4.25	4.05	3.22	4.05
Weight of Dry Soil	g	10.27	10.86	8.92	11.58
Water Content, W	%	41.38	37.29	36.10	34.97



Liquid Limit, LL = 37.62 %
 Plastic Limit, PL = 31.86 %
 Plasticity Index, PI = 5.75 %
 Water content, W_n = _____ %

Remarks: 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Patong Phuket
 Borehole No. PT_2.50Well Sample No. 1 Depth 2.50 m
 Soil Description Brown Granitics Soil Tested by THIPMANEE Date 27/1/2004

Plastic Limit

Container No.		s17	s6	s1	s4	
Weight of Wet Soil+Container	g	6.37	7.48	8.11	7.31	
Weight of Dry Soil+Container	g	6.01	6.88	7.32	6.74	
Weight of Container	g	4.93	4.96	4.94	4.94	
Weight of Water	g	0.36	0.60	0.79	0.57	
Weight of Dry Soil	g	1.08	1.92	2.38	1.80	
Water Content, W	%	33.33	31.25	33.19	31.67	
Average	%	32.36				

Liquid Limit

Number of Blows		10	16	21	26	32	43
Container No.		s3	s9	s5	s2	s16	s14
Weight of Wet Soil+Container	g	20.27	17.54	20.77	18.62	19.90	16.57
Weight of Dry Soil+Container	g	15.99	14.12	16.57	15.04	16.16	13.65
Weight of Container	g	4.94	4.91	4.91	4.86	5.02	5.05
Weight of Water	g	4.28	3.42	4.2	3.58	3.74	2.92
Weight of Dry Soil	g	11.05	9.21	11.66	10.18	11.14	8.60
Water Content, W	%	38.73	37.13	36.02	35.17	33.57	33.95



Liquid Limit, LL = 35.33 %
 Plastic Limit, PL = 32.36 %
 Plasticity Index, PI = 2.97 %
 Water content, W_n = _____ %

Remarks: 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Patong Phuket
 Borehole No. PT_3.00Well Sample No. 1 Depth 3.00 m
 Soil Description Brown Granitics Soil Tested by THIPMANEE Date 15/1/2004

Plastic Limit

Container No.	D2	A3	C9	C1	
Weight of Wet Soil+Container	g 21.76	19.75	21.37	20.73	
Weight of Dry Soil+Container	g 20.80	18.79	20.00	19.96	
Weight of Container	g 17.34	15.31	15.59	17.21	
Weight of Water	g 0.96	0.96	1.37	0.77	
Weight of Dry Soil	g 3.46	3.48	4.41	2.75	
Water Content, W	% 27.75	27.59	31.07	28.00	
Average	%	28.60			

Liquid Limit

Number of Blows	14	20	31	45	59	
Container No.	B4	D3	C6	A4	D4	
Weight of Wet Soil+Container	g 35.27	31.92	37.82	44.50	35.60	
Weight of Dry Soil+Container	g 30.16	27.78	32.25	38.15	30.96	
Weight of Container	g 15.05	14.96	14.40	16.83	14.80	
Weight of Water	g 5.11	4.14	5.57	6.35	4.64	
Weight of Dry Soil	g 15.11	12.82	17.85	21.32	16.16	
Water Content, W	% 33.82	32.29	31.20	29.78	28.71	



Liquid Limit, LL = 31.75 %
 Plastic Limit, PL = 28.60 %
 Plasticity Index, PI = 3.15 %
 Water content, W_n = _____ %

Remarks: 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Patong Phuket
 Borehole No. PT_1.80LS Sample No. 1 Depth 1.80 m
 Soil Description Brown Clayey Sand Tested by THIPMANEE Date 27/1/2004

Plastic Limit

Container No.	s25	s12	s18	s22	
Weight of Wet Soil+Container	g 8.83	6.57	8.65	8.08	
Weight of Dry Soil+Container	g 7.91	6.18	7.72	7.32	
Weight of Container	g 4.96	4.95	4.91	4.96	
Weight of Water	g 0.92	0.39	0.93	0.76	
Weight of Dry Soil	g 2.95	1.23	2.81	2.36	
Water Content, W	% 31.19	31.71	33.10	32.20	
Average	% 32.05				

Liquid Limit

Number of Blows	15	18	27	31	39	42
Container No.	s8	s20	s24	s10	s19	s7
Weight of Wet Soil+Container	g 17.71	16.36	17.61	16.96	15.77	17.25
Weight of Dry Soil+Container	g 13.79	12.91	13.89	13.49	12.67	13.73
Weight of Container	g 4.93	4.90	4.93	5.00	4.96	4.92
Weight of Water	g 3.92	3.45	3.72	3.47	3.10	3.52
Weight of Dry Soil	g 8.86	8.01	8.96	8.49	7.71	8.81
Water Content, W	% 44.24	43.07	41.52	40.87	40.21	39.95



Liquid Limit, LL = 44.29 %
 Plastic Limit, PL = 32.05 %
 Plasticity Index, PI = 12.24 %
 Water content, W_n = _____ %

- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

ATTERBERG'S LIMITS TEST


Project Landslide Behavior in Phuket Location: Patong Phuket
 Borehole No. PT_4.00LS Sample No. 1 Depth 4.00 m
 Soil Description Brown Sand Tested by THIPMANEE Date 28/1/2004

Plastic Limit

Container No.	s14	s2	s4	s17	
Weight of Wet Soil+Container	g 8.44	7.63	6.97	6.72	
Weight of Dry Soil+Container	g 7.66	7.02	6.51	6.31	
Weight of Container	g 5.05	4.86	4.94	4.93	
Weight of Water	g 0.78	0.61	0.46	0.41	
Weight of Dry Soil	g 2.61	2.16	1.57	1.38	
Water Content, W	% 29.89	28.24	29.30	29.71	
Average	% 29.28				

Liquid Limit

Number of Blows	13	17	21	37	43	
Container No.	s11	s13	s16	s5	s1	
Weight of Wet Soil+Container	g 17.43	18.77	19.77	16.07	14.98	
Weight of Dry Soil+Container	g 14.08	15.01	15.83	13.22	12.46	
Weight of Container	g 5.26	4.90	5.02	4.91	4.95	
Weight of Water	g 3.35	3.76	3.94	2.85	2.52	
Weight of Dry Soil	g 8.82	10.11	10.81	8.31	7.51	
Water Content, W	% 37.98	37.19	36.45	34.30	33.56	



Liquid Limit, LL = 35.69 %
 Plastic Limit, PL = 29.28 %
 Plasticity Index, PI = 6.40 %
 Water content, W_n = _____ %

Remarks: 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

PERMEABILITY TEST (ASTM D 2434)

PROJECT Landslide Behavior in Phuket OWNER _____ BORING NO. _____
 SOIL DISCRPTION Brown Clayey Sand LOCATION Patong Phuket SAMPLE DEPTH 0.00-2.20
 TESTED BY _____ DATE 07-01-48

SAMPLE DATA :

SAMPLE DIAMETER	<u>3.812</u> cm.	WEIGHT OF MOLD + SOIL	<u>633.56</u> gm.
SAME HEIGHT	<u>7.752</u> cm.	WEIGHT OF MOLD	<u>477.24</u> gm.
SAMEPLE AREA	<u>11.407</u> cm. ²	WEIGHT OF SOIL	<u>156.32</u> gm.
SAMPLE VOLUME	<u>88.428</u> cm. ³	DENSITY OF SOIL	<u>1.77</u> gm/cm. ³
TYPE OF SAMPLE	<u>DISTURBED</u>	TESTING HEAD	<u>400</u> cm.

CONSTANT HEAD PERMEABILITY TEST :

TRIAL NO.	TIME (sec)	Q (cc)	T (c)	TRIAL NO.	TIME (sec)	Q (cc)	T (c)
1	60.25	0.77	25	6	60.22	0.73	25
2	61.29	0.78	25	7	60.31	0.66	25
3	60.29	0.74	25	8	60.25	0.66	25
4	60.28	0.75	25	9	60.44	0.79	25
5	60.59	0.76	25	10	60.53	0.66	25
Average Values					60.45	0.73	

SOIL PERMEABILITY k : 2.05E-05 cm./sec.

VARIABLE HEAD PERMEABILITY TEST : AREA OF STANDPIPE _____ cm.²

TRIAL NO.	h ₁ (sec)	h ₁ (sec)	TIME (sec)	TRIAL NO.	h ₁ (sec)	h ₁ (sec)	TIME (sec)
1				6			
2				7			
3				8			
4				9			
5				10			
Average Values							

SOIL PERMEABILITY k : _____ cm./sec.

- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABORATORY

PERMEABILITY TEST (ASTM D 2434)

PROJECT Landslide Behavior in Phuket OWNER _____ BORING NO. _____
 SOIL DISCRPTION Red Clayey Sand LOCATION Kamala Phuket SAMPLE DEPTH 0.00-1.50
 TESTED BY _____ DATE 30-12-47

SAMPLE DATA :

SAMPLE DIAMETER	<u>3.862</u> cm.	WEIGHT OF MOLD + SOIL	<u>643.18</u> gm.
SAME HEIGHT	<u>7.912</u> cm.	WEIGHT OF MOLD	<u>477.4</u> gm.
SAMEPLE AREA	<u>11.708</u> cm. ²	WEIGHT OF SOIL	<u>165.78</u> gm.
SAMPLE VOLUME	<u>92.636</u> cm. ³	DENSITY OF SOIL	<u>1.79</u> gm/cm. ³
TYPE OF SAMPLE	<u>DISTURBED</u>	TESTING HEAD	<u>400</u> cm.

CONSTANT HEAD PERMEABILITY TEST :

TRIAL NO.	TIME (sec)	Q (cc)	T (c)	TRIAL NO.	TIME (sec)	Q (cc)	T (c)
1	60.09	0.37	25	6	60.10	0.36	25
2	60.22	0.43	25	7	60.09	0.37	25
3	60.24	0.43	25	8	60.10	0.36	25
4	60.22	0.43	25	9	60.22	0.42	25
5	60.21	0.42	25	10	60.25	0.43	25
Average Values					60.17	0.40	

SOIL PERMEABILITY k : 1.13E-05 cm./sec.

VARIABLE HEAD PERMEABILITY TEST : AREA OF STANDPIPE _____ cm.²

TRIAL NO.	h ₁ (sec)	h ₁ (sec)	TIME (sec)	TRIAL NO.	h ₁ (sec)	h ₁ (sec)	TIME (sec)
1				6			
2				7			
3				8			
4				9			
5				10			
Average Values							

SOIL PERMEABILITY k : _____ cm./sec.

- Remarks:
- 1) Certification applies to test samples only.
 - 2) Information under "For", "Project", are supplied by client. These are not certified.
 - 3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project	Landslide Behavior in Phuket	
Soil Description	Red Clayey Sand	
Diameter of Sample	6.330	cm.
Hight of Sample	2.540	cm.
Area of Sample	31.454	cm. ²
Volume	79.893	cm. ³
Type of Test	Multi Stage Direct Shear Test	
	Consolidation Drained Test	

Location	Patong Phuket	BORING NO.	KML1well
Proving Ring No.	1155-15-11838		
Shearing Rate	0.01 mm/min		
Test by:	THIPMANEE		

Container No.	H1		
Wet soil+Container	g. 161.38		
Dry soil+Container	g. 127.81		
Weight of Water	g. 33.57		
Weight Container	g. 18.60		
Weight of Dry Soil	g. 109.21		
Water Content	% 30.74		
Average Water Content	% 30.74		

Specific Gravity	2.612
Unit Weight	ton/m ³ 1.800
Void Ratio	0.745
Degree of Saturation	% 107.79



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.126	0.223
2	0.190	0.265
3	0.269	0.326
4	0.395	0.414
5	0.584	0.577
$\phi = 37.67$ Degree		$c = 0.1197$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	KML1well
Sr ; %	51.97

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY


DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY

DIRECT SHEAR TEST (ASTM D 3080)

Project	Landslide Behavior in Phuket		Location	Patong Phuket	BORING NO.	KML1well
Soil Description	Red Clayey Sand		Proving Ring No.		1155-15-11838	
Diameter of Sample	6.330	cm.	Shearing Rate		0.01 mm/min	
Hight of Sample	2.540	cm.	Test by:		THIPMANEE	
Area of Sample	31.454	cm. ²				
Volume	79.893	cm. ³				
Type of Test	Multi Stage Direct Shear Test					
	Consolidation Drained Test					

	D6	A7	140
Wet soil+Container	g. 50.67	38.59	140.98
Dry soil+Container	g. 45.92	35.35	126.53
Weight of Water	g. 4.75	3.24	14.45
Weight Container	g. 15.53	14.08	20.26
Weight of Dry Soil	g. 30.39	21.27	106.27
Water Content	% 15.63	15.23	13.60
Average Water Content	% 14.82		

Specific Gravity	2.612
Unit Weight	ton/m ³ 1.800
Void Ratio	0.745
Degree of Saturation	% 51.97



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.189	1.546
2	0.253	1.502
3	0.379	1.637
4	0.569	1.870
5	0.727	2.064
$\phi = 46.26$ Degree		c = 1.2814 ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	KML1well
Sr ; %	76.39

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY


DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY

DIRECT SHEAR TEST (ASTM D 3080)

Project	Landslide Behavior in Phuket		Location	Patong Phuket	BORING NO.	KML1well
Soil Description	Red Clayey Sand		Proving Ring No.		1155-15-11838	
Diameter of Sample	6.330	cm.	Shearing Rate		0.01 mm/min	
Hight of Sample	2.540	cm.	Test by:		THIPMANEE	
Area of Sample	31.454	cm. ²				
Volume	79.893	cm. ³				
Type of Test	Multi Stage Direct Shear Test					
	Consolidation Drained Test					

	D6	B3	H3
Wet soil+Container	51.99	60.66	150.18
Dry soil+Container	45.78	52.43	127.4
Weight of Water	6.21	8.23	22.78
Weight Container	15.53	18.02	18.43
Weight of Dry Soil	30.25	34.41	108.97
Water Content	20.53	23.92	20.90
Average Water Content	21.78		

Specific Gravity	2.612
Unit Weight	1.800
Void Ratio	0.745
Degree of Saturation	76.39



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.126	1.113
2	0.190	1.016
3	0.269	1.078
4	0.395	1.212
5		
$\phi = 25.82$ Degree		$c = 0.9863$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	KML1well
Sr ; %	85.79

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY


DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY

DIRECT SHEAR TEST (ASTM D 3080)

Project	Landslide Behavior in Phuket		Location	Patong Phuket	BORING NO.	KML1well
Soil Description	Red Clayey Sand		Proving Ring No.		1155-15-11838	
Diameter of Sample	6.330	cm.	Shearing Rate		0.01 mm/min	
Hight of Sample	2.540	cm.	Test by:		THIPMANEE	
Area of Sample	31.454	cm. ²				
Volume	79.893	cm. ³				
Type of Test	Multi Stage Direct Shear Test Consolidation Drained Test					

Container No.		A4	A7	
Wet soil+Container	g.	60.98	51.65	
Dry soil+Container	g.	52.23	44.33	
Weight of Water	g.	8.75	7.32	
Weight Container	g.	16.85	14.08	
Weight of Dry Soil	g.	35.38	30.25	
Water Content	%	24.73	24.20	
Average Water Content	%	24.46		

Specific Gravity	2.612
Unit Weight	ton/m ³ 1.800
Void Ratio	0.745
Degree of Saturation	% 85.79



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.126	0.309
2	0.190	0.345
3	0.269	0.386
4	0.395	0.462
5	0.584	0.590
$\phi = 31.46$ Degree		$c = 0.227$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	KML1well
Sr ; %	107.79

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project	Landslide Behavior in Phuket	
Soil Description	Brown Granitics Soil	
Diameter of Sample	6.330	cm.
Hight of Sample	2.540	cm.
Area of Sample	31.454	cm. ²
Volume	79.893	cm. ³
Type of Test	Multi Stage Direct Shear Test	
	Consolidation Drained Test	

Location	Patong Phuket	BORING NO.	KML2well
Proving Ring No.	1155-15-11838		
Shearing Rate	0.01 mm/min		
Test by:	THIPMANEE		

Container No.	H5		
Wet soil+Container	g. 165.34		
Dry soil+Container	g. 128.57		
Weigth of Water	g. 36.77		
Weight Container	g. 18.43		
Weigth of Dry Soil	g. 110.14		
Water Content	% 33.38		
Average Water Content	% 33.38		

Specific Gravity	2.607
Unit Weight	ton/m ³ 1.779
Void Ratio	0.792
Degree of Saturation	% 109.89



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.189	0.256
2	0.253	0.324
3	0.379	0.462
4		
5		
$\phi = 47.38$ Degree		$c = 0.00495$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	KML2well
Sr ; %	34.52

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Granitics Soil
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. KML2well
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

Container No.	B3	A4	H5
Wet soil+Container	g. 56.91	38.47	134.49
Dry soil+Container	g. 52.75	36.55	124.19
Weight of Water	g. 4.16	1.92	10.30
Weight Container	g. 18.02	16.84	18.44
Weight of Dry Soil	g. 34.73	19.71	105.75
Water Content	% 11.98	9.74	9.74
Average Water Content	% 10.49		

Specific Gravity	2.607
Unit Weight	ton/m ³ 1.779
Void Ratio	0.792
Degree of Saturation	% 34.52



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.189	1.698
2	0.253	1.512
3	0.379	1.539
4	0.569	1.646
5	0.727	1.776
$\phi = 15.39$ Degree		$c = 1.5177$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	KML2well
Sr ; %	46.43

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Granitics Soil
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. KML2well
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

Container No.	B3	G21	H5
Wet soil+Container	g. 37.15	38.89	137.55
Dry soil+Container	g. 34.65	36.89	121.76
Weigth of Water	g. 2.50	2.00	15.79
Weight Container	g. 18.02	20.98	14.45
Weigth of Dry Soil	g. 16.63	15.91	107.31
Water Content	% 15.03	12.57	14.71
Average Water Content	% 14.11		

Specific Gravity	2.607
Unit Weight	ton/m ³ 1.779
Void Ratio	0.792
Degree of Saturation	% 46.43



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.189	1.251
2	0.253	1.285
3	0.379	1.408
4	0.569	1.570
5		
$\phi = 40.72$ Degree		$c = 1.0795$ ksc.


Remark:
 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	KML2well
Sr ; %	66.75

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Granitics Soil
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. KML2well
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

Container No.	D6	B3	H5
Wet soil+Container	g. 37.78	63.17	138.48
Dry soil+Container	g. 34.24	54.95	118.77
Weight of Water	g. 3.54	8.22	19.71
Weight Container	g. 15.54	18.03	18.43
Weight of Dry Soil	g. 18.70	36.92	100.34
Water Content	% 18.93	22.26	19.64
Average Water Content	% 20.28		

Specific Gravity	2.607
Unit Weight	ton/m ³ 1.779
Void Ratio	0.792
Degree of Saturation	% 66.75



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.190	0.669
2	0.253	0.710
3	0.379	0.771
4	0.569	0.897
5	0.695	1.000
$\phi = 32.70$ Degree		$c = 0.5416$ ksc.


Remark:
 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	KML2well
Sr ; %	81.62

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY


DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY

DIRECT SHEAR TEST (ASTM D 3080)

Project	Landslide Behavior in Phuket		Location	Patong Phuket	BORING NO.	KML2well
Soil Description	Brown Granitics Soil		Proving Ring No.		1155-15-11838	
Diameter of Sample	6.330	cm.	Shearing Rate		0.01 mm/min	
Hight of Sample	2.540	cm.	Test by:		THIPMANEE	
Area of Sample	31.454	cm. ²				
Volume	79.893	cm. ³				
Type of Test	Multi Stage Direct Shear Test					
	Consolidation Drained Test					

Container No.		H1		
Wet soil+Container	g.	142.00		
Dry soil+Container	g.	117.48		
Weight of Water	g.	24.52		
Weight Container	g.	18.59		
Weight of Dry Soil	g.	98.89		
Water Content	%	24.80		
Average Water Content	%	24.80		

Specific Gravity		2.607
Unit Weight	ton/m ³	1.779
Void Ratio		0.792
Degree of Saturation	%	81.62



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.190	0.567
2	0.253	0.581
3	0.379	0.684
4	0.569	0.814
5	0.569	0.814
$\phi = 34.27$ Degree		$c = 0.4246$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	KML2well
Sr ; %	109.89

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project	Landslide Behavior in Phuket	
Soil Description	Brown Granitics Soil	
Diameter of Sample	6.330	cm.
Hight of Sample	2.540	cm.
Area of Sample	31.454	cm. ²
Volume	79.893	cm. ³
Type of Test	Multi Stage Direct Shear Test	
	Consolidation Drained Test	

Location	Patong Phuket	BORING NO.	PT3well
Proving Ring No.	1155-15-11838		
Shearing Rate	0.01 mm/min		
Test by:	THIPMANEE		

Container No.	H1		
Wet soil+Container	g. 131.99		
Dry soil+Container	g. 101.92		
Weigth of Water	g. 30.07		
Weight Container	g. 16.80		
Weigth of Dry Soil	g. 85.12		
Water Content	% 35.33		
Average Water Content	% 35.33		

Specific Gravity	2.638
Unit Weight	ton/m ³ 1.667
Void Ratio	0.903
Degree of Saturation	% 103.24



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.177
2	0.319	0.251
3	0.508	0.379
4	0.634	0.477
5		
$\phi = 37.35$ Degree		$c = 0.0065$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT3well
Sr ; %	34.66

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY


DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY

DIRECT SHEAR TEST (ASTM D 3080)

Project	Landslide Behavior in Phuket		Location	Patong Phuket	BORING NO.	PT3well
Soil Description	Brown Granitics Soil		Proving Ring No.		1155-15-11838	
Diameter of Sample	6.330	cm.	Shearing Rate		0.01 mm/min	
Hight of Sample	2.540	cm.	Test by:		THIPMANEE	
Area of Sample	31.454	cm. ²				
Volume	79.893	cm. ³				
Type of Test	Multi Stage Direct Shear Test					
	Consolidation Drained Test					

	φ40	φ200	
Wet soil+Container	g. 38.43	44.66	
Dry soil+Container	g. 36.5	42.05	
Weight of Water	g. 1.93	2.61	
Weight Container	g. 20.45	19.74	
Weight of Dry Soil	g. 16.05	22.31	
Water Content	% 12.02	11.70	
Average Water Content	%	11.86	

Specific Gravity	2.638
Unit Weight	ton/m ³ 1.667
Void Ratio	0.903
Degree of Saturation	% 34.66



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.566
2	0.316	0.621
3	0.506	0.728
4	0.632	0.833
5	0.790	0.919
$\phi = 33.36$ Degree		c = 0.4042 ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT3well
Sr ; %	47.18

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY


DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY

DIRECT SHEAR TEST (ASTM D 3080)

Project	Landslide Behavior in Phuket		Location	Patong Phuket	BORING NO.	PT3well
Soil Description	Brown Granitics Soil		Proving Ring No.		1155-15-11838	
Diameter of Sample	6.330	cm.	Shearing Rate		0.01 mm/min	
Hight of Sample	2.540	cm.	Test by:		THIPMANEE	
Area of Sample	31.454	cm. ²				
Volume	79.893	cm. ³				
Type of Test	Multi Stage Direct Shear Test					
	Consolidation Drained Test					

	A4	A60	
Wet soil+Container	g. 49.29	49.94	
Dry soil+Container	g. 44.93	45.45	
Weight of Water	g. 4.36	4.49	
Weight Container	g. 16.85	18.66	
Weight of Dry Soil	g. 28.08	26.79	
Water Content	% 15.53	16.76	
Average Water Content	%	16.14	

Specific Gravity		2.638
Unit Weight	ton/m ³	1.667
Void Ratio		0.903
Degree of Saturation	%	47.18



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.466
2	0.316	0.516
3	0.506	0.636
4	0.632	0.736
5		
$\phi = 35.07$ Degree		$c = 0.2887$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT3well
Sr ; %	77.38

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Granitics Soil
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. PT3well
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

Container No.	H1	๓40	๓200
Wet soil+Container	g. 139.54	47.66	57.27
Dry soil+Container	g. 114.41	41.98	49.33
Weight of Water	g. 25.13	5.68	7.94
Weight Container	g. 18.61	20.44	19.74
Weight of Dry Soil	g. 95.80	21.54	29.59
Water Content	% 26.23	26.37	26.83
Average Water Content	% 26.48		

Specific Gravity	2.638
Unit Weight	ton/m ³ 1.667
Void Ratio	0.903
Degree of Saturation	% 77.38



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.353
2	0.316	0.390
3	0.505	0.516
4	0.632	0.637
5		
$\phi = 36.64$ Degree		$c = 0.1565$ ksc.


Remark:
 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT3well
Sr ; %	93.91

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Granitics Soil
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. PT3well
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

	H1	D6	A4
Wet soil+Container	150.46	58.79	68.91
Dry soil+Container	119.31	48.19	55.99
Weight of Water	31.15	10.60	12.92
Weight Container	18.61	15.55	16.84
Weight of Dry Soil	100.70	32.64	39.15
Water Content	30.93	32.48	33.00
Average Water Content	32.14		

Specific Gravity	2.638
Unit Weight	1.667 ton/m ³
Void Ratio	0.903
Degree of Saturation	93.91 %



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.272
2	0.316	0.356
3	0.506	0.502
4	0.632	0.618
5		
$\phi = 41.46$ Degree		$c = 0.0596$ ksc.


Remark:
 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT3well
Sr ; %	103.24

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Sand
 Diameter of Sample 6.330
 Hight of Sample 2.540
 Area of Sample 31.454
 Volume 79.893
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. PT4LS
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

Container No.	A
Wet soil+Container	g. 144.52
Dry soil+Container	g. 117.22
Weigth of Water	g. 27.30
Weight Container	g. 18.59
Weigth of Dry Soil	g. 98.63
Water Content	% 27.68

Specific Gravity	2.646
Unit Weight	ton/m ³ 1.653
Void Ratio	0.889
Degree of Saturation	% 82.42



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.166
2	0.316	0.229
3	0.505	0.336
4	0.632	0.429
5		
$\phi = 33.76$ Degree		$c = 0.0046$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT4LS
Sr ; %	80.42

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY


DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY

DIRECT SHEAR TEST (ASTM D 3080)

Project	Landslide Behavior in Phuket		Location	Patong Phuket	BORING NO.	PT4LS
Soil Description	Brown Sand		Proving Ring No.		1155-15-11838	
Diameter of Sample	6.330	cm.	Shearing Rate		0.01 mm/min	
Hight of Sample	2.540	cm.	Test by:		THIPMANEE	
Area of Sample	31.454	cm. ²				
Volume	79.893	cm. ³				
Type of Test	Multi Stage Direct Shear Test					
	Consolidation Drained Test					

	A	D6	B3
Wet soil+Container	g. 138.67	59	73.92
Dry soil+Container	g. 113.75	49.54	62.03
Weigth of Water	g. 24.92	9.46	11.89
Weight Container	g. 18.60	15.53	18.02
Weigth of Dry Soil	g. 95.15	34.01	44.01
Water Content	% 26.19	27.82	27.02
Average Water Content	%	27.01	

Specific Gravity	2.646
Unit Weight	ton/m ³ 1.653
Void Ratio	0.889
Degree of Saturation	% 80.42



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.235
2	0.316	0.288
3	0.505	0.425
4	0.632	0.521
5		
$\phi = 36.94$ Degree		$c = 0.0462$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT4LS
Sr ; %	82.42

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Sand
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. PT4LS
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

	A	D6	
Wet soil+Container	g. 56.62	57.93	
Dry soil+Container	g. 49.12	50.67	
Weigth of Water	g. 7.50	7.26	
Weight Container	g. 15.54	18.03	
Weigth of Dry Soil	g. 33.58	32.64	
Water Content	% 22.33	22.24	
Average Water Content	%	22.29	

Specific Gravity	2.646
Unit Weight	ton/m ³ 1.653
Void Ratio	0.889
Degree of Saturation	% 66.37



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.326
2	0.316	0.392
3	0.505	0.502
4	0.632	0.604
5		
$\phi = 35.20$ Degree		$c = 0.1543$ ksc.


Remark:
 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT4LS
Sr ; %	66.37

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Sand
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. PT4LS
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

Container No.	B3	A4	
Wet soil+Container	g. 63.83	41.73	
Dry soil+Container	g. 57.39	38.27	
Weight of Water	g. 6.44	3.46	
Weight Container	g. 18.03	16.86	
Weight of Dry Soil	g. 39.36	21.41	
Water Content	% 16.36	16.16	
Average Water Content	% 16.26		

Specific Gravity	2.646
Unit Weight	ton/m ³ 1.653
Void Ratio	0.889
Degree of Saturation	% 48.42



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.521
2	0.316	0.579
3	0.505	0.669
4	0.632	0.732
5	0.790	0.912
$\phi = 33.96$ Degree		$c = 0.3462$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT4LS
Sr ; %	59.57

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Sand
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. PT4LS
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

Container No.	A	D6	B3
Wet soil+Container	g. 137.32	53.73	50.1
Dry soil+Container	g. 117.43	47.05	44.64
Weight of Water	g. 19.89	6.68	5.46
Weight Container	g. 18.60	14.07	16.84
Weight of Dry Soil	g. 98.83	32.98	27.80
Water Content	% 20.13	20.25	19.64
Average Water Content	% 20.01		

Specific Gravity	2.646
Unit Weight	ton/m ³ 1.653
Void Ratio	0.889
Degree of Saturation	% 59.57



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.379
2	0.316	0.420
3	0.505	0.529
4	0.632	0.645
5		
$\phi = 34.38$ Degree		$c = 0.2008$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT4LS
Sr ; %	48.42

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Sand
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. PT4LS
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

Container No.	B3	G21	
Wet soil+Container	g. 43.75	44.23	
Dry soil+Container	g. 40.71	41.15	
Weight of Water	g. 3.04	3.08	
Weight Container	g. 18.02	20.99	
Weight of Dry Soil	g. 22.69	20.16	
Water Content	% 13.40	15.28	
Average Water Content	%	14.34	

Specific Gravity	2.646
Unit Weight	ton/m ³ 1.653
Void Ratio	0.889
Degree of Saturation	% 42.69



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.599
2	0.316	0.658
3	0.506	0.785
4		
5		
$\phi = 35.86$ Degree		$c = 0.4213$ ksc.


Remark:
 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT4LS
Sr ; %	42.69

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Sand
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. PT4LS
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

Container No.	A1	D6	B3
Wet soil+Container	g. 139.51	38.58	45.05
Dry soil+Container	g. 125.95	35.74	42.04
Weight of Water	g. 13.56	2.84	3.01
Weight Container	g. 20.23	15.54	18.03
Weight of Dry Soil	g. 105.72	20.20	24.01
Water Content	% 12.83	14.06	12.54
Average Water Content	% 13.14		

Specific Gravity	2.646
Unit Weight	ton/m ³ 1.653
Void Ratio	0.889
Degree of Saturation	% 39.13



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	0.764
2	0.316	0.836
3	0.506	0.949
4	0.632	1.029
5		
$\phi = 33.91$ Degree		$c = 0.6075$ ksc.

Remark:


- 1) Certification applies to test samples only.
- 2) Information under "For", "Project", are supplied by client. These are not certified.
- 3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT4LS
Sr ; %	39.13

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.




Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.




KASETSART UNIVERSITY
DEPARTMENT OF CIVIL ENGINEERING
GEOTECHNICAL ENGINEERING LABORATORY

Project:	Landslide Behavior in Phuket
Boring No.	PT4LS
Sr ; %	29.97

Shear Stress and Displacement,mm.



Vertical and Horizontal Displacement,mm.



- Remarks: 1) Certification applies to test samples only.
2) Information under "For", "Project", are supplied by client. These are not certified.
3) This certificate is invalid without appropriate signature and seal.



KASETSART UNIVERSITY

DEPARTMENT OF CIVIL ENGINEERING, GEOTECHNICAL ENGINEERING LABOLATORY


DIRECT SHEAR TEST (ASTM D 3080)

Project Landslide Behavior in Phuket
 Soil Description Brown Sand
 Diameter of Sample 6.330 cm.
 Hight of Sample 2.540 cm.
 Area of Sample 31.454 cm.²
 Volume 79.893 cm.³
 Type of Test Multi Stage Direct Shear Test
Consolidation Drained Test

Location Patong Phuket BORING NO. PT4LS
 Proving Ring No. 1155-15-11838
 Shearing Rate 0.01 mm/min
 Test by: THIPMANEE

Container No.	H1	A4	A7
Wet soil+Container	g. 128.19	47.85	35.54
Dry soil+Container	g. 118.53	44.74	33.7
Weight of Water	g. 9.66	3.11	1.84
Weight Container	g. 18.60	16.85	14.07
Weight of Dry Soil	g. 99.93	27.89	19.63
Water Content	% 9.67	11.15	9.37
Average Water Content	%	10.06	

Specific Gravity	2.646
Unit Weight	ton/m ³ 1.653
Void Ratio	0.889
Degree of Saturation	% 29.97



Test No.	Normal Stress ksc.	Max Shear Stress ksc.
1	0.255	1.140
2	0.315	1.162
3	0.504	1.193
4	0.630	1.229
5	0.789	1.276
$\phi = 13.64$ Degree		$c = 1.0792$ ksc.

Remark:
 1) Certification applies to test samples only.
 2) Information under "For", "Project", are supplied by client. These are not certified.
 3) This certificate is invalid without appropriate signature and seal.