

งานวิจัยครั้งนี้มีวัตถุประสงค์ 1) เพื่อศึกษาถึงสาเหตุการส่งมอบงานการก่อสร้างสถานีไฟฟ้าย่อย ถ้าชำเกินกำหนดตามสัญญาในเขตพื้นที่จังหวัดสมุทรสาครตามความคิดเห็นของผู้ว่าจ้างและผู้รับจ้าง และ 2) เพื่อเปรียบเทียบความคิดเห็นระหว่างผู้ว่าจ้างกับผู้รับจ้างเกี่ยวกับสาเหตุที่ทำให้เกิดการส่งมอบงานการก่อสร้างสถานีไฟฟ้าย่อย ถ้าชำเกินกำหนดตามสัญญาในเขตพื้นที่จังหวัดสมุทรสาคร เก็บรวบรวมข้อมูลด้วยแบบสอบถามจากกลุ่มตัวอย่าง จำนวน 108 คน วิเคราะห์ข้อมูลด้วยค่าความถี่ ค่าร้อยละ ค่าเฉลี่ย ค่าเบี่ยงเบนมาตรฐาน และการทดสอบสมมติฐานด้วยการทดสอบค่าที่

ผลการวิจัยพบว่า

1. ความคิดเห็นเกี่ยวกับสาเหตุที่ทำให้เกิดการส่งมอบงานการก่อสร้างสถานีไฟฟ้าย่อย ถ้าชำเกินกำหนดตามสัญญา ในเขตพื้นที่จังหวัดสมุทรสาครของผู้ว่าจ้างและผู้รับจ้างโดยรวมทั้ง 5 ด้าน มีความคิดเห็นอยู่ในระดับปานกลาง เมื่อพิจารณารายด้านพบว่า ปัจจัยด้านการเงินมีสาเหตุในระดับสูงสุด รองลงมาเป็นด้านบุคคล ด้านการจัดการงานก่อสร้าง ด้านเครื่องจักร และด้านวัสดุเป็นปัจจัยที่มีสาเหตุระดับต่ำที่สุด ตามลำดับ

2. ความคิดเห็นเกี่ยวกับสาเหตุของการส่งมอบงานก่อสร้างสถานีไฟฟ้าย่อย ถ้าชำเกินกำหนดตามสัญญา ระหว่างผู้ว่าจ้างและผู้รับจ้าง โดยรวมมีความคิดเห็นแตกต่างกันอย่างมีนัยสำคัญทางสถิติที่ระดับ 0.05

The purposes of this research were to : 1) study the cause of electrical sub-station construction delays in Samutsakon Province and 2) to compare the opinion about cause of electrical sub-station construction delays in Samutsakon Province between employers and contractors. The concerning person of constructive project were selected as purposive sampling. The sample were 108 persons. The tool of data collection were the questionnaires which suitable application from Likert scale. The Quantitative datas were canalized by computer. The data were analyzed to determine frequency, percentage, means, standard deviation, and t-test was applied for testing the hypotheses.

The research results were as the following :

1. As a whole, the opinion about cause of electrical sub-station construction delays in Samutsakon Province were in the average level. According to available statistics, the sequent of cause were at a highly important level, where as financial, personel, management, and machine, were the second importance and material was considered as the least importance.

2. When the opinion cause of electrical sub-station construction delays in Samutsakon Province were broken down by employers and contractors it as a whole was important that had significant at 0.05 level as stated in the hypotheses.